

KINGDOM OF CAMBODIA

PHNOM PENH WATER SUPPLY AUTHORITY


Urban Water Supply Management in PHNOM PENH, CAMBODIA

PRESENTED BY MR. LONG NARO DEPUTY DIRECTOR GENERAL OF PPWSA

26 November 2015



- I. GENERAL OVERVIEW
- II. PRESENT WATER SUPPLY SYSTEM
- III. EXPANSION OF WATER SYSTEM 2014-2017
- IV. FUTURE PROJECT 2017-2021
- V. EXTERNAL ACTIVITIES AND PARTNERSHIP
- VI. BUSINESS OPPORTUNITIES



I. General Overview

- From 1980-1992 was returned back from the civil war. The Phnom Penh Water Supply Company was operated under authority of Phnom Penh Municipality with full subsidiary.
- From 1993-1996 with the support from the Royal Government of Cambodia, foreign donors and international organizations, the Company was transformed into the public enterprise under subdegree 52, December 1996. New Director General was assigned in September 1993.





I. General Overview (cont.)

- External Assistance were committed to support PPWSA such as UNDP/World Bank/Asian Development Bank/France/Japan.
- Study on first Master Plan was conducted in 1993 by JICA (1993-2010)
- Urgent rehabilitation and improvement of the existing water supply facilities have began including strengthening of operational management and capacity building to the employees.





I. General Overview (cont.)

- From August 1997-2012 was formed as public enterprise with full financial and administrative autonomy controlled by Board of Directors.
- Completion of rehabilitation of the existing water supply facilities by starting for expansion of water supply system in 2002 to the suburb area of the city.
- Study on second master plan was funded by JICA for 2005-2020.





I. General Overview (cont.)

• From April 2012 until now Phnom Penh Water Supply is a public listing enterprise,15% of asset was sold to the shareholder and 85% is controlled by the government. The enterprise is managed by Board of Director. Former Director General retired in June 2012. A New Director General was assigned in September 2013.

Foreign Assistance 1993-2014

Foreign Assistance	Grant	Loan
UNDP/World Bank	2,803,000	
World Bank		29,455,000
Asian Development Bank		12,639,000
France	21,248,500	39,461,500
Japan	72,454,440	44,407,560
TOTAL	96,505,940	125,963,060
TOTAL GRANT and LOAN	222,	469,000

Japanese Assistance

Description	Input
Source of Finance	Loan from JICA for WTP and Intake by AFD (Co-finance)
Type of Contract	Design and Built
Implementation Period	August 2010- February 2013
Contractor	Moya Asia Limited
Consultant	Safege
Capacity	130,000 m3/day
Cost of the project for WTP and Intake	40,336,206 USD 14,697,371 USD





Benefit from the Project (Niroth Phase I)

- Increasing of water production capacity from 300,000 m3/day to 430,000m3/day.
- 24 hr water supply with average pressure in the network over 20 m.
- Southern/western part of the city receiving better service.
- Water quality complied to WHO standard with full time water quality monitoring system.





Benefit from the Project (Niroth Phase I)

- Full automation for the operational management of water treatment plan.
- Optimization of energy use by introducing variable speed driver (Invertor).
- Simple water treatment plant process with optimized maintenance cost.
- Most of the design such as sizing, space, backwash system and electrical facilities have been prepared for Niroth Phase II followed Master Plan.






Niroth Phase I









Evolution of Water Consumption in Each Sangkat (commune) in 2014, After Completion of Niroth Phase I.





Japanese Assistance (Grant Aid)



Benefit from the Project (Solar Energy)

Description	Unit	Quantity
Solar energy generation (777kWh)	kWh/year	< 1,000,000
Average electricity consumption At Phum Prek WTP	kWh/year	16,321,000
Average electricity cost	USD/kWh	0.2
Annual electricity saving	USD	200,000
Annual electricity cost	USD	3,231,960
Solar energy saving	%	6% to 8%
CO ₂ reduction	Tons/year	640



II. Present Water Supply System

A. Water Production

Production Capacity: 430,000 m3/day



II. Present Water Supply System (cont.)

B. Water Network

This principle gradients Interprinciple gra

1,892 1,753

Length of Constructed Pipe

- Water Transmission Main 500-1600 mm diameter : Ductile Cast Iron Pipe.
- Main Distribution Pipe 250-400 mm diameter: Ductile Cast Iron Pipe
- Distribution Pipe from 50 to 200 mm dia. : HDPE
- House connection : HDPE and volumetric meter.

Result of Operational Management

1993	INDICATORS		2014
20	Staff / 1,000 connections		2.97
65,000	Production capacity, m ³ /day		430,000
???	Water quality		WHO
280 km	Distribution		2,312 km
20%	Coverage area		85%
10 hr/d	Supply duration		24 hr/d
0.2 bar	Supply pressure		2 bar
26,881	Number of connections		270,812
72%	NRW		7.72%
48%	Collection efficiency		99.9%
150%	Operation ratio		35.56%
N/A	Return on revenue	V	24.84%
N/A	Return on net asset	y.	7.06%
N/A	Current ratio		4.57 times
N/A	Debt service coverage		2.57 times
N/A	Accounts receivable		21 days

II.EXPANSION PROJECT 2014-217

On-going Project


- Source of Financing : AFD (France).
- AFD Loan No. : CKH 1121 01F
- Amount of Loan: 30,000,000 Euro
- Project duration: 2013-2017
- PPWSA counterpart: cover 90 % civil work payment for construction of Niroth Phase II. 100% of civil work payment for installation of water transmission and distribution pipe.
- Description of the Project :
 - > Expansion of Niroth Phase II 130,000 m3/day





On-going Project (cont.)

- > Replacement of district meters with additional district meters from 41 to 117 Zonings.
- ➤ Replacement of existing telemeter by autonomous GSM data logger for data transmission such as flow pressure.
- Improvement/upgrading of existing SCADA by making the SCADA accessible through a web interface.
- ➤ Installation of GIS system for the Asset Management, (distribution mapping, customer mapping).



On-going Project (cont.)

- > Expansion of Water Transmission Main of 36 km.
- Expansion of Distribution Pipe of 500 km.








On-going Project (cont.)

Summary of Project Budget 2014-2017


	# Va. 10					
ITE	DESCRIPTION OF THE PROJECT	AFD FINANCE	PPWSA FINANCE	Total		
M						
1.	Niroth Phase II	14,025,520	12,256,315	26,281,835		
2.	Consultant Service	1,893,913		1,893,913		
3.	Water Transmission Main	8,764,850	4,382,425	13,147,275		
4.	Distribution Pipe	4,204,255	1,657,624	5,861,878		
5.	GIS Project	486,277		486,277		
6.	Flow-meter	284,180		284,180		
7.	GSM data logger +SCADA	400,000		400,000		
8.	Installation cost for zoning		360,000	360,000		
9.	Contingency	3,001,20 0		3,001,200		
	Grand Total	33,000,000	18,656,364	51,716,558		
	WITTED CHIPPLI					
	WAITH SOLL					

IV. Future Project 2017-2021



Year	2015	2016	2017	2018	2019	2020	2021
DEMAND	445,500	475,800	506,500	543,200	578,700	620,000	664,100
PRODUTION	430,00	470,000	540,000	592,000	592,000	592,000	762,000
NEW PLANT		60,000	70,000	52,000	<u>50,000</u>		170,000

1) Geographical repartition of the water demand




- The following map was created by allocating to each existing WTP (including Niroth 2) a service area corresponding to their respective production capacities and the Transmission Mains architecture. All unserved areas were subsequently allocated to the new Northern Resource which shall be called Prek Tasek WTP.
- That map shows that the service area of existing WTPs will be significantly shrinked, especially Niroth which will barely serve Chom Chao anymore.
- The service area of Prek Tasek is in the shape of a bow that stretches from the north to the south-west of the city.
 Evolution of water demand will lead to a non-optimal map of water transmission whereby very long water transfers will be rendered necessary. That is because existing WTPs will not be able to serve those areas anymore.
- Therefore, in addition to the overall production capacity deficit by 2030, a second problem arises which is the service areas of each WTP. It may not be optimal to produce 100% of future needs from the north when a significant part of the deficit will be located in the south.

2) Transmission Network


How the new WPF are going to be integrated in the overall Phnom Penh water transmission network?

The following figure provides an example of a flow matrix, the thickness of the arrows representing the daily flow in each pipe and the colour representing the origin of the water. In grey are the existing water distribution pipes.





3) Network expansion




In considering network expansion over the period 2015-2030, we considered that 12 additional sangkats would get connected, whereas the remaining 10 would not get water from the network by 2030.

4) Number of connections

Those figures are high, but we would like to remind that the GPPWSS feasibility study plan 16 000 new connections which seemed excessive by the time; but two years later, actual figures – in a context of lack of water resource – were already above 18 000 connections/year.

Therefore we believe that a forecast of 16 000 to 21 000 new connections per year is ambitious but yet realistic, and those numbers can be achieved by PPWSA.



5) CAPEX

Cost estimates are based on real rates observed for Niroth 1 and Niroth 2 construction, modified when necessary, and adjusted for 2017 costs.

		170 MLD	170MLD	340 MLD	Chamcar Morn	West Resource	TOTAL
		Phase I	Phase II	Total	52 MLD	50 MLD	in USD
1		Water F	Production Fac	ilities 170 MLC)		
	General Cost	5,860,006	5,860,006	11,720,012	2,961,000	2,353,627	17,034,639
	E&M Equipment	24,026,783	15,818,360	39,845,143	8,287,500	5,422,596	53,555,239
	Civil Works	38,633,355	19,789,343	58,422,698	9,975,000	8,282,186	76,679,884
	Total WPF	68,520,144	41,467,709	109,987,853	21,223,500	16,058,409	147,269,762
2		Raw	Water Transm	nission Main			
	Pipe & Fitting	7,652,598		7,652,598	258,200		7,910,798
	Pipe Laying	3,816,299		3,816,299	103,300		3,919,599
	Total RWTM	11,468,897	0	11,468,897	361,500		11,830,397
3		Treate	d Water Trans	mission Main			
	Pipe & Fitting	25,974,800		25,974,800	183,000		26,157,800
	Pipe Laying	10,389,920		10,389,920	67,200		10,457,120
	Total TWTM	36,364,720		36,364,720	250,200		36,614,920
4			Consultant S	ervice			
	Project supervision	4,653,350	1,658,708	6,312,058	1,041,400	642,366	7,995,824
	Total Consultant Service	4,653,350	1,658,708	6,312,058	1,041,400	642,366	7,995,824
5			Contingen	cies			
	Physical Contingencies	2,538,672	1,293,793	3,832,465	980,300	501,002	
	Price Contingencies	5,816,688	2,073,385	7,890,073	1,307,100	802,920	
	Total Contingencies	8,355,360	3,367,178	11,722,538	2,287,400	1,303,922	0
	TOTAL PROJECT COST	129,362,471	46,493,595	175,856,066	25,164,000	18,004,697	203,710,903
	Financing from loan	76,502,898	26,704,253	103,207,151	15,098,400	10,802,818	129,108,369
	PPWSA own funds	52,839,574	19,789,343	72,628,917	10,065,600	7,201,879	89,896,396

V. EXTERNAL ACTIVITIES AND PARTNERSHIP

Water Supply and Sanitation subsidiary was created on 19th April 2012, under the control of Phnom Penh Water Supply Authority (PPWSA) and located in PPWSA compound. The main tasks of the subsidiary is to manage daily activities for the installation of water transmission and distributing pipeline accordance with the annual plan of PPWSA, cooperating with Water Production and Water Distribution Department for the major water leakage repairing of water pipe and to act as private company on behalf of PPWSA to cooperate with private partnership to perform extra income on the field of clean water and sanitation specialized on design, supervision, construction, capacity building and NRW contract in the country and abroad.

Person in-charge: Mr. Long Naro, Deputy Director General of PPWSA

Address: Phnom Penh Water Supply Authority (PPWSA)

Office No. 45, Street No. 106, Sangkat Sras Chark, Daun Penh District,

Phnom Penh Cambodia.

Tel: 855 12 211 211/855 977711113

E-mail: long_naro@yahoo.com or long_naro@ppwsa.com.kh

Web: www.ppwsa.com.kh

V. EXTERNAL ACTIVITIES AND PARTNERSHIP

(Project No. I)					
1	Location of Project	Pursat and Battambang Provincial Capital			
2	Type of Project	Sub-contractor to Kubota Construction Company			
3	Project Period	2012-2013			
4.1	Project Scope	Pursat Province			
Expan	sion Length	9,440 m			
Replac	cement Length	5,160 m			
4.2	Project Scope	Battambang Province			
Pipe E	xpansion Length	24,480 m			
Pipe R	eplacement Length	21,550 m			
Service	e Pipe Length	25,580 m			
5	Financing Source	JICA Grant Aid			





V. EXTERNAL ACTIVITIES AND PARTNERSHIP

Title of the Project: The Project for Expansion of Water Supply System in Kompong Cham and Battambang Provincial Capitals (Project No. II)

Battambang Provincial Capitals (Project No. II)					
1	Location of Project	Kompong Cham and Battambang Provincial Capital			
2	Type of Project	Sub-contractor to Kubota Construction Company (Civil Works)			
3	Project Period	2014-2016			
4	Project Scope	Pipe installation of raw water transmission main and distribution pipeline			
Battambang Province		53,850 m			
Kompong Cham Province		49,300 m			
5 F	inancing Source	JICA Grant Aid			





VI. BUSINESS OPPORTUNITIES

Based on the UN report in the first half of 2015, 277 million people in Asia and the Pacific still lacked access to safe drinking water despite significant progress since 1990. To meet sustainable development goal No. 6 (SDG) by 2030 "Universal and Equitable Access to Safe and Affordable Drinking Water for All", PPWSA has commit and cooperate with government, external financing organizations and investors to overcome the programme as presented in the slide for "Future Project". Within this regards, the business opportunities for the consultant contractors, manufacturers and suppliers could not absent to the following field:

- 1. Consultant for design and supervision of constructions.
- 2. Contractor for construction of water treatment plan.

THE WATER

- 3. Manufacturers for pumps, valve, HDPE pipe, DCIP pipe, electrical equipment and other.
- 4. Contractors work with the PPWSA-subsidiary for the other project in the country.







CAMBODIA: THE COUNTRY OF WONDER

THANK YOU AND COME TO VISIT CAMBODIA

